

SIX NINE CONSTRUCTION (PVT) LTD

PROJECT: Strickland Lodge Motel - Budgetary Quote
QUOTATION ID: SNC-STRICKLAND-QT-2026-001 | **REVISION:** 1
CLIENT: Eastern Highlands Trust / Strickland Lodge

Item Description	Unit	Quantity	Rate (\$)	Total (\$)
Site establishment and rain protection	item	1.00	9,500.00	9,500.00
Clearing, levels and cart-away	m2	420.00	9.50	3,990.00
Substructure and DPM	m2	316.00	122.00	38,552.00
Ground slab and screed	m2	316.00	68.00	21,488.00
Masonry walls and partitions	m2	560.00	78.00	43,680.00
RC columns, beams and lintels	item	1.00	24,500.00	24,500.00
Roof structure and coverings	m2	380.00	105.00	39,900.00
Plaster, skim and paint	m2	1,120.00	19.50	21,840.00
Ceilings and cornices	m2	316.00	37.00	11,692.00
Floor finishes	m2	316.00	38.00	12,008.00
Wet-area tiling	m2	205.00	46.00	9,430.00
Doors and ironmongery	no	24.00	420.00	10,080.00
Windows, glazing and bars	no	22.00	365.00	8,030.00
Plumbing and sanitary works	item	1.00	33,500.00	33,500.00
Electrical installation	m2	316.00	58.00	18,328.00
Cupboards, kitchens and joinery	item	1.00	28,500.00	28,500.00
Verandahs and external concrete	m2	90.00	72.00	6,480.00
Stormwater and erosion control	item	1.00	14,500.00	14,500.00
Clean, snagging and handover	item	1.00	6,500.00	6,500.00
Direct Costs:				\$362,498.00
Preliminaries:				\$28,500.00
Overheads:				\$39,099.80
Contingency:				\$48,874.75
Profit Margin:				\$70,379.64
Provisional Sums:				\$42,000.00
Discounts:				-\$0.00
ZIMRA VAT:				\$88,702.83
GRAND TOTAL:				\$680,055.02

Assumptions

- Budgetary pricing only: derived from one A3 floor-plan PDF with no structural, MEP, elevation, finish, soil, survey, or specification pack.
- Pricing is in USD and assumes October to mid-March Zimbabwe rainy-season work, including productivity loss, protection, wet-weather access, stormwater diversion, and programme risk.
- Measured allowance assumes approximately 316 m2 enclosed floor area and approximately 380 m2 roof/covered envelope, subject to CAD/BIM or IFC remeasurement.
- Rates assume conventional masonry construction, reinforced concrete substructure and slab, standard lodge-grade finishes, and normal day-shift labour.
- No client budget was provided; pricing is cost-plus with overhead, rainy-season contingency, provisional sums, and profit separated for audit.

- Final tender must be revised after site visit, soil confirmation, finish schedule, door/window schedule, sanitary schedule, electrical layout, drainage design, and supplier quotations.

Exclusions

- Land, statutory approvals, professional fees, utility connection fees, permits, levies, and authority charges.
- Abnormal ground, rock excavation, exceptional dewatering, contaminated material, retaining walls, major earthworks, and off-site roadworks.
- Furniture, loose appliances, curtains, linen, signage, landscaping, borehole/water storage, solar/PV, generator, air-conditioning, CCTV, Wi-Fi, and specialist lodge equipment.
- Price escalation, foreign-exchange movement, customs/duty shocks, and material price changes beyond quote validity.
- Any scope not visible or inferable from the single floor-plan drawing.

Audit Trail & Pricing Integrity Signature

Secure Checksum: d506e4c7f33d25ff4a2405354f478263ed3ae14ff866c7a3fac2c2aaf7b8de2b